



4x4 Bus Stop -Materials List

Shopping List

Framing

One	Hemlock	4x6x4'	Skids
Four	Hemlock	2x6x8'	Floor joists, Rafters
One	Hemlock	2x6x8'	Rim joists
Four	Hemlock	1x6x8'	Floor Boards,
Four	Hemlock	4x4x8'	Posts, braces
Two	Hemlock	4x4x8'	Beams
Ten	Hemlock	1x4x8'	Roof strapping, temporary bracing
Two	Hemlock	2x4x10'	Wall Nailers
One	Hemlock	2x4x12'	Door Studs
Two	Hemlock	2x4x8'	Wall Framing

Siding

One	Pine	1x6x8'	Ledger Board (ridge pole)
Five	Pine	1x12x8'	Bearing wall Siding
Eight	Pine	1x12x8'	Siding
Two	Pine	1x12'x10'	Siding

Trim

One	Pine	1x8x10'	Fascia
Two	Pine	1x8x8'	Fascia, Siding
Four	Pine	1x4x8'	Corner
Four	Pine	1x4x8'	door, shadow trim
Two	Pine	1x4x8'	door, shadow trim, corner
Three	Pine	1x5x8'	Door Casing
One	Pine	1x5x4'	Kick Plate

Hardware

- Nails 6lbs 3 1/2" spikes (16's) 4 lbs 2" galvanized (8's)
- Corrugated Metal Roofing choice of color
 - Two sheets @ 19"
 - Two sheets @ 74"
 - 54" of matching ridge cap
 - 75 1 1/2" wood grip screws with rubber gasket, matching color to roof
- One 1/4" Hex drive bit for roofing screws
- Optional one square feet of roofing material, wood shingles, metal, asphalt, slate
- Optional if roofing material other than metal is used the roof should be sheathed solid, add seven pine 1x12'x10'

An allowance for mistakes and waste has been included

Please contact us with any mistakes or discrepancies in these plans. We strive to provide our clients with a quality product and encourage feedback.



Hardware Package

Contact us today to purchase a Hardware Package to match this set of plans.



4x6 Bus Stop Material List

Floor- Hemlock

1-4x6x12' Skids
1-2x6x12' Rim Joists
2-2x6x8' Joists
4-1x6x12' Floor Boards

Trim-Pine

1-1x8x14' Fascia
1-1x8x8' Fascia
1-1x4x14' Shadow
4-1x4x12 Corner /Door Trim
2-1x4x10' Corner/Door Trim
1-1x7x6' Kick plate
1-1x10x10' Rip to 5" For Casing

Walls-Hemlock

1-4x4x14' Posts
2-4x4x12' Beams, Braces
2-2x4x12' Nailer, Header
1-2x4x10' Nailer

Interior Bench

1-1x4x12' Rim Joists
1-2x4x8' Bench Joists
1-1x8x6' Bench Top
1-1x10x6' Bench Top

Roof-Hemlock

2-2x6x12' Rafters
1-2x6x8' Rafters
1-2x4x4' Rfater Supports
1-x8x6' Ledger Board
3-1x4x12' Strapping

Hardware

6bs-16D Framing Nails
8lbs-8D HDG Hand Nails-Galv
100-Roofing Screws

1-1/4" Hex Bit

Temp Bracing/ Extra Lumber

1-1x4x12' Hemlock
1-1x4x8' Hemlock
1-1x12x8' - Pine

Corrugated Roofing

3 Pieces of roofing @19"
3-Pieces Ridge Cap @74"
1Piece of Ridge Cap @ 82"

Siding-Pine

1-1x12x14'
1-1x12x12'
5-1x12x10'
2-1x12x8'
1-1x8x14'
2-1x8x8'

Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar)
25' tape measure Chalk line Extension Cord Tin
Snips
Staple gun
Pencil
Speed Square Four-foot level Cordless Drill
1/4" drive bit for drill