



## 12x16 Harvester-4 Season Material List

### Floor

2-6x6x16' Skids-Hemlock  
4-2x6x16' Rim-joist & blocking-KD Spruce  
9-2x6x12' Rim Joist /Floor Joist-KD Spruce

### Walls-Hemlock

6-4x4x16' Posts & Beams  
2-4x4x12' -Gable Beams  
4-4x4x10' -Angle Braces  
4-2x4x14' Wall Framing & Insulation nailers  
11-2x4x12' Wall Framing & Insulation nailers  
18-2x4x10' Wall Framing & Insulation nailers

### Roof

3-2x6x16' KD Spruce-Collar ties  
18-2x6x12' KD Spruce-Rafters  
  
18-1x12x16' Pine-Roof Sheathing  
  
1-1x8x16' Pine- Ridge Pole

### Temp Bracing/ Extra Lumber

3-2x4x12' Hemlock-Extra  
1-1x12x16' Pine- Extra  
1-1x12x16' -SHIP-LAP-Extra  
5-1x4x12' Hemlock- Temp Braces

### Interior

2-2x4x12' Hemlock-Loft joists  
9-1x12x12' Pine Loft Decking  
1-1x4x12' Loft Trim

### Exterior Siding-Pine

6-1x12x16'  
10-1x12x14'  
8-1x12x12'  
34-1x12x10'  
4-1x6x10'

### Interior Siding- Ship-Lap Pine

26-1x10x16'  
8-1x12x14''  
12-1x12x12'  
34-1x12x10'

### Battens--Pine- rip to 3/4"

2-2x8x14' Battens  
3-2x4x12'  
14-2x8x10' Battens

### Trim-Pine

8-2x8x10' -Fascia  
1-2x4x14' Shadow  
2-2x4x12' Shadow  
4-2x4x10' Shadow  
  
6-1x4x16' Window/ Door Trim  
3-1x4x14' Window/Door Trim  
1-1x4x12' Window/Door Trim  
11-1x4x10' Corner trim /Window Trim



## **12x16 Harvester-4 Season Mill Work & Hardware**

### **Mill-work**

1-3-0x6-8 Nine Lite Steel Door-LHIS  
2-3x2 Sliding Insulated Windows  
1-2x2 Awning Insulated Windows

### **Additional Lumber**

6 -3/4" 4x8 CDX Plywood  
6 -3/8" 4x8 CDX Plywood

### **Hardware**

12bs-16D Framing Nails-3-1/2"  
5bs-16D Galvanized Framing Nails-3-1/2"  
18lbs-8D Galvanized Hand Nails  
10lbs-6D Galvanized Hand Nails  
400-Roofing Screws-1-1/2"  
  
1-1/4" Hex Bit  
  
Locking Door Hardware Kit-H.K.DOOR

### **Corrugated Roofing**

12- Pieces of Roofing @116"  
2-Pieces of Ridge Cap @ 126"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips  
#3 Square Drive Razor Knife Chisel

### **Interior**

105 Ft of WeatherMate Vapor Barrier  
10 Pieces @18' of TRI-FLEX Vapor Barrier  
510 SqFt R-21 5-1/2" -24"OC Fiberglass Insulation  
20-4x8x1-3/4" Rigid Foam Insulation  
Foil Backed  
60' of 3" Bituthene Strips

**Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.**



## 12x20 Harvester-4 Season Material List

### Floor

4-2x6x16' Skids-Hemlock  
8-2x6x12' Skids-Hemlock  
1-2x6x16' Rim-joist-KD Spruce  
13-2x6x12' Rim Joist /Floor Joist-KD Spruce  
4-2x6x10' Joist Blocking -KD Spruce

### Walls-Hemlock

7-4x4x16' Posts & Beams  
7-4x4x12' Angle Braces-Gable Beams  
5-2x4x16' Wall Framing & Insulation nailers  
16-2x4x12' Wall Framing & Insulation nailers  
19-2x4x10' Wall Framing & Insulation nailers

### Roof

3-2x6x16' KD Spruce-Collar ties  
22-2x6x12' KD Spruce-Rafters  
  
9-1x12x16' Pine-Roof Sheathing  
18-1x12x12' Pine-Roof Sheathing  
  
1-1x8x12' Pine- Ridge Pole  
1-1x8x8' Pine- Ridge Pole

### Temp Bracing/ Extra Lumber

1-2x6x16' Hemlock-Extra  
2-2x4x10' Hemlock-Extra  
1-1x12x16' Pine- Extra  
1-1x12x16'-SHIP-LAP-Extra  
5-1x4x12' Hemlock- Temp Braces

### Interior

1-4x4x8'-Hemlock-Loft Post  
8-2x6x16' Hemlock-Loft  
12-1x10x16' Ship-Lap Pine-Loft Decking  
1-1x6x16'-Pine-Loft Tim

### Exterior Siding-Pine

6-1x12x16'  
8-1x12x14'  
10-1x12x12'  
41-1x12x10'  
1-1x8x8'  
2-1x6x10'

### Interior Siding- Ship-Lap Pine

17-1x10x16'  
8-1x12x14''  
18-1x12x12'  
56-1x12x10'

### Battens--Pine- rip to 3/4"

2-2x8x14' Battens  
3-2x4x12'  
14-2x8x10' Battens

### Trim-Pine

2-2x8x14'-Fascia  
6-2x8x10' Fascia  
  
4-2x4x12' Shadow  
4-2x4x10' Shadow  
5-1x4x16' Window/ Door Trim  
3-1x4x14' Window/Door Trim  
1-1x4x12' Window/Door Trim  
11-1x4x10' Corner trim /Window Trim



## **12x20 Harvester-4 Season Mill Work & Hardware**

### **Mill-work**

1-3-0x6-8 Nine Lite Steel Door-LHIS  
2-3x2 Sliding Insulated Windows  
1-2x2 Awning Insulated Windows

### **Additional Lumber**

8 -3/4" 4x8 CDX Plywood  
8 -3/8" 4x8 CDX Plywood

### **Hardware**

12bs-16D Framing Nails-3-1/2"  
5bs-16D Galvanized Framing Nails-3-1/2"  
20lbs-8D Galvanized Hand Nails  
12lbs-6D Galvanized Hand Nails  
500-Roofing Screws-1-1/2"  
  
1-1/4" Hex Bit  
  
Locking Door Hardware Kit-H.K.DOOR

### **Corrugated Roofing**

16- Pieces of Roofing @116"  
2-Pieces of Ridge Cap @ 126"  
1-Pieces of Ridge Cap @ 42"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips  
#3 Square Drive Razor Knife Chisel

### **Interior**

129 Ft of WeatherMate Vapor Barrier  
10 Pieces @22' of TRI-FLEX Vapor Barrier  
680 SqFt R-21 5-1/2" -24"OC Fiberglass Insulation  
22-4x8x1-3/4" Rigid Foam Insulation  
Foil Backed  
60' of 3" Bituthene Strips

**Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.**



## 12x24 Harvester-4 Season Material List

### Floor

12-2x6x16' Skids-Hemlock  
3-2x6x16' Rim-joist -KD Spruce  
17-2x6x12' Floor Joist & Blocking-KD Spruce

### Walls-Hemlock

7-4x4x16' Posts & Beams  
6-4x4x12'-Gable Beams & Angle Braces  
2-4x4x10' Beams  
7-2x4x16' Wall Framing & Insulation nailers  
2-2x4x14' Wall Framing & Insulation nailers  
10-2x4x12' Wall Framing & Insulation nailers  
25-2x4x10' Wall Framing & Insulation nailers

### Roof

4-2x6x16' KD Spruce-Collar ties  
26-2x6x12' KD Spruce-Rafters  
  
27-1x12x16' Pine-Roof Sheathing  
  
2-1x8x12' Pine- Ridge Pole

### Temp Bracing/ Extra Lumber

3-2x4x12' Hemlock-Extra  
1-1x12x16' Pine- Extra  
1-1x12x16'-SHIP-LAP-Extra  
5-1x4x12' Hemlock- Temp Braces

### Interior

2-2x4x12' Hemlock-Loft joists  
9-1x12x12' Pine Loft Decking  
1-1x4x12' Loft Trim

### Exterior Siding-Pine

8-1x12x16'  
8-1x12x14'  
8-1x12x12'  
50-1x12x10'  
4-1x6x10'

### Interior Siding- Ship-Lap Pine

36-1x10x16'  
8-1x12x14"  
12-1x12x12'  
52-1x12x10'

### Battens--Pine- rip to 3/4"

2-2x8x14' Battens  
-2x4x12'  
14-2x8x10' Battens

### Trim-Pine

4-2x8x14' Fascia  
4-2x8x10'-Fascia  
  
2-2x4x16' Shadow  
6-2x4x10' Shadow  
  
7-1x4x16' Window/ Door Trim  
3-1x4x14' Window/Door Trim  
3-1x4x12' Window/Door Trim  
8-1x4x10' Corner trim /Window Trim



## **12x24 Harvester-4 Season Mill Work & Hardware**

### **Mill-work**

1-3-0x6-8 Nine Lite Steel Door-LHIS  
2-3x2 Sliding Insulated Windows  
1-2x2 Awning Insulated Windows

### **Additional Lumber**

9 -3/4" 4x8 CDX Plywood  
9 -3/8" 4x8 CDX Plywood

### **Hardware**

12bs-16D Framing Nails-3-1/2"  
5bs-16D Galvanized Framing Nails-3-1/2"  
18lbs-8D Galvanized Hand Nails  
10lbs-6D Galvanized Hand Nails  
400-Roofing Screws-1-1/2"  
  
1-1/4" Hex Bit  
  
Locking Door Hardware Kit-H.K.DOOR

### **Corrugated Roofing**

18- Pieces of Roofing @116"  
2-Pieces of Ridge Cap @ 126"  
2-Pieces of Ridge Cap @ 82"

### **Suggested Tools**

Skill Saw or Hand saw Saw-z-all or chain saw  
Hammer  
Nail puller (cats paw or crow bar)  
25' tape measure Chalk line Extension Cord Tin  
Snips  
Staple gun  
Pencil  
Speed Square Four-foot level Cordless Drill  
1/4" drive bit for drill  
#2 Phillips  
#3 Square Drive Razor Knife Chisel

### **Interior**

105 Ft of WeatherMate Vapor Barrier  
10 Pieces @18' of TRI-FLEX Vapor Barrier  
510 SqFt R-21 5-1/2" -24"OC Fiberglass Insulation  
20-4x8x1-3/4" Rigid Foam Insulation  
Foil Backed  
60' of 3" Bituthene Strips

**Cutting will be necessary to complete the kit. Some boards may need to be cut to length. Rough openings for door and window will need to be cut out. Some trim boards may need to be ripped to width.**