



6x4 Gable Material List

Floor- Hemlock

1-4x6x12' Skids
1-2x4x12' Rim Joists
2-2x4x8' Joists
4-1x6x12' Floor Boards

Walls-Hemlock

1-4x4x14' Posts
3-4x4x12' Beams, Braces
1-2x4x12' Nailer, Header
2-2x4x8' Nailer
1-2x4x12' KD SPRUCE

Roof-Hemlock

2-2x4x10' Rafters
1-1x6x6' Ridge
1-1x4x12' Strapping
1-1x4x16' Strapping, Collar tie

Temp Bracing/ Extra Lumber

2-1x4x8' Hemlock
1-1x4x6' Hemlock
1-1x12x8' - Pine

Siding-Pine

4-1x12x14'
2-1x12x10'
5-1x12x8'
2-1x6x8'

Trim-Pine

2-1x6x10' Fascia
2-1x6x10' Fascia
3-1x6x14' -Rip to 1x3 for trim
1-1x4x8' Rip to 1x2 for stops

Millwork

JCS built 5-0 Double doors- 2@30-1/8" x71-3/8"

Hardware

5bs-16D Framing Nails
5lbs-8D HDG Hand Nails-Galv
100-Roofing Screws

1-1/4" Hex Bit
1-#2 Square Drive Bit

4-8" Black Door Hinges
1-Turn Latch Black
40-Door Hinge Screws-Black

Corrugated Roofing

4 Pieces of roofing @45"
1-Pieces Ridge Cap @56"



8x4 Utility Shed Material List

Floor- Hemlock

1-4x6x8' Skids
1-2x4x12' Joists
3-2x4x8' Rim Joists/Joists
9-1x6x8' Floor Boards

Walls-Hemlock

3-4x4x12' Posts Angle Braces
2-4x4x8'-Beams
1-2x4x14' Nailer, Header
2-2x4x12' Nailer
1-2x4x8' Blocking

Roof-Hemlock

3-2x4x10' Rafters
1-1x6x8' Ridge/ Collar ties
4-1x4x8' Strapping

Temp Bracing/ Extra Lumber

2-1x4x8' Hemlock
1-1x4x6' Hemlock
1-1x12x8' - Pine

Siding-Pine

16-1x12x8'
2-1x12x16'
1-1x6x14'

Trim-Pine

3-1x6x10' Fascia
1-1x4x14' Corner Trim
4-1x4x12' Corner/ door Trim
1-1x4x8'
1-1x6x6'-Rip to 2'' - RIP TWICE

Millwork

JCS built 5-0 Double doors- 2@30-1/8" x71-3/8"

Hardware

5bs-16D Framing Nails
5lbs-8D HDG Hand Nails-Galv
100-Roofing Screws
20- 1-5/8" Exterior Screws

1-1/4" Hex Bit
1-#2 Square Drive Bit

4-8" Black Door Hinges
1-Turn Latch Black
40-Door Hinge Screws-Black

Corrugated Roofing

4 Pieces of roofing @56"
1-Pieces Ridge Cap @56"



10x4 Utility Shed Material List

Floor- Hemlock

1-4x6x10' Skids
1-2x4x10' Rim Joists
3-2x4x8' Joists
8-1x6x10' Floor Boards

Walls-Hemlock

2-4x4x14' Posts & Beams
1-2x4x14' Nailer & Header
2-2x4x12' Beams & Door studs
4-2x4x8' Angle Braces & Blocking

Roof-Hemlock

3-2x4x12' Rafters
1-1x6x10' Ridge & Collar Tie
4-1x4x8' Strapping

Temp Bracing/ Extra Lumber

2-1x4x10' Hemlock
1-2x4x10' Hemlock
1-1x12x10' - Pine

Siding-Pine

5-1x12x14'
4-1x12x12'
5-1x12x8'
2-1x6x10'

Trim-Pine

2-1x6x12' Fascia
1-1x6x10' Fascia
3-1x6x14' -Rip to 1x3 for trim
1-1x4x12' Rip to 1x2 for stops

Millwork

JCS built 5-0 Double doors(A)
2@30-1/8" x71-3/8"

Hardware

4bs-16D Framing Nails
5lbs-8D HDG Hand Nails-Galv
100-Roofing Screws

1-1/4" Hex Bit
1-#2 Square Drive Bit

4-8" Black Door Hinges
1-Turn Latch Black
40-Door Hinge Screws-Black
1 Chain Bolt
1 Foot Bolt

Corrugated Roofing

4 Pieces of Roofing @68"
1-Pieces Ridge Cap @56"

Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar)
25' tape measure Chalk line Extension Cord Tin Snips
Staple gun
Pencil
Speed Square Four-foot level Cordless Drill
1/4" drive bit for drill
#2 Phillips
#3 Square Drive Razor Knife Chisel