



4x8 Woodbin Material List

Floor

HEMLOCK

- (2) 4x6x8' Skids
- (1) 2x6x12' Floor Joists
- (3) 2x6x8' Floor Joists, Rim Joists
- (8) 1x6x8' Floor Boards

Framing

HEMLOCK

- (9) 4x4x8' Posts, Beams, Braces
- (1) 2x4x14' Nailers
- (2) 2x4x12' Nailers
- (1) 1x4x10' Temp Bracing
- (3) 1x4x8' Temp Bracing

Roof

HEMLOCK

- (5) 2x6x8' Rafters
- (1) 2x4x8' Rafter Supports,
Floor Partition Nailer
- (1) 1x8x8' Ledger Board
- (6) 1x4x8' Strapping

Siding

PINE

- (3) 1x12x16' Siding
- (2) 1x12x12' Siding
- (4) 1x12x10' Siding
- (1) 1x10x6' Siding
- (2) 1x8x8' Siding

Trim

PINE

- (2) 2x8x10' Fascia
- (2) 2x8x8' Fascia
- (1) 2x4x14' Vertical Partition Nailers
- (4) 2x4x10' Shadow
- (2) 1x10x8' Door Casing (Rip to 5")
- (2) 1x4x14' Corner Trim
- (2) 1x4x12' Corner Trim
- (2) 1x4x10' Door Trim

Extra Lumber

PINE

- 1x4x8' Extra Lumber
- 1x12x8' Extra Lumber

Hardware

- (5lbs) 16D Framing Nails
- (3lbs) 16D HDG Nails
- (5lbs) 8D Nails
- (175) 1-1/2" Roofing Screws
- (1) 1/4" Hex Bit

Corrugated Metal Roofing

- (3) Pieces at 74"
- (3) Pieces at 19"
- (1) Ridge Cap at 106"



4x10 Woodbin Material List

Floor- Hemlock

2-4x6x10' Skids
2-2x6x10' Rim Joists
3-2x6x8' Joists
8-1x6x10' Decking

Walls-Hemlock

4-4x4x10' Beams & Angle Braces
4-4x4x8' Posts & Beams
1-2x4x12' Door Studs
2-2x4x10' Nailers & Door Header
4-2x4x8' Nailers & Partition

Roof-Hemlock

6-2x6x8' Rafters
1-2x4x8' Rafter Supports
1-1x8x10' Ledger Board
6-1x4x10' Roof Strapping

Temp Bracing/ Extra Lumber

1-1x4x12' Hemlock
2-1x4x10' Hemlock
1-1x12x10' - Pine

Siding-Pine

1-1x12x12'
8-1x12x10'
6-1x12x8'
1-1x10x8'
2-1x8x8'
1-1x4x4'

Hardware

5bs-16D Framing Nails
8lbs-8D HDG Hand Nails
2-lbs-6D HDG Nails
125-Roofing Screws

1-1/4" Hex Bit
1-#2 Square Drive Bit

8-8" Black Door Hinges
2-Turn Latch Black
80-Door Hinge Screws-Black
2-Chain Bolts
2-Foot Bolts

Corrugated Roofing

4 Pieces of roofing @74"
4 Pieces of roofing @19"
2-Pieces Ridge Cap @72"

Trim-Pine

1-1x8x12' Fascia
1-1x8x10'
2-1x8x8'
1-1x4x12' Corner/Door/Shadow Trim
4-1x4x10'
8-1x4x8'
1-1x7x10' Kick Plate
1-1x10x10' Rip to 5" for Door casing



4x12 Woodbin Material List

Floor- Hemlock

2-4x6x12' Skids
2-2x6x12' Rim Joists
4-2x6x8' Joists
8-1x6x12' Floor Boards

Walls-Hemlock

1-4x4x16' Posts- Rear Beam
1-4x4x14'- Posts
4-4x4x12- Beams- Braces
1-4x4x8' Braces
1-2x6x14' Partition
1-2x4x16' Door header and Blocking
1-2x4x14' Door studs
1-2x4x12' Nailers

Roof-Hemlock

7-2x6x8' Rafters
1-2x4x8' Rafter Supports
1-1x8x12' Ledger
6-1x4x12' Strapping

Temp Bracing/ Extra Lumber

2-1x4x12' Hemlock
2-1x4x8' Hemlock
1-1x12x12'- Pine
1-1x4x12'- Pine

Siding-Pine

2-1x12x14'
1-1x12x12'
6-1x12x10'
5-1x12x8'
1-1x10x8'
2-1x8x10'
1-1x4x8'

Trim-Pine

6-1x8x8' Fascia
6-1x4x8' Shadow
1-1x4x14' Door Trim
6-1x4x10' Corner Trim

2-1x10x8' RIP to 5"

Hardware

5 Lbs 16D Nails
3 Lbs 16D HDG Nails
6 Lbs 8D Nails
150- 1-1/2" Roofing Screws
1-1/4" Hex Bit

Corrugated Roofing

5 Pieces @ 74"
5 Pieces @ 19"
1 Ridge cap @ 126"
1 Ridge Cap @ 44"



Jamaica Cottage Shop, Inc.
 Post Office Box 106 Jamaica, Vermont 05343
 Voice 802 297 3760 Fax 802 297 2825
plans@JamaicaCottageShop.com

6x10 Woodbin Material List

Use this list as a shopping list.
 Rough sawn Lumber

Please contact us with any mistakes or discrepancies in these plans. We strive to provide our clients with a quality product and encourage feedback.

Floor (Hemlock)	Walls (Hemlock)	Roof (Hemlock)	Siding (Pine)	Trim (Pine)	Extra
(2) 4x6x10'	(1) 4x6x10'	(6) 2x6x10'	(7) 1x12x12'	(1) 2x8x10'	(4) 1x4x8' (Hem.)
(2) 2x6x10'	(3) 4x4x14'	(5) 1x4x10'	(1) 1x12x12'	(2) 2x8x12'	
(4) 2x6x10'	(2) 4x4x12'	(2) 1x4x8'	(9) 1x12x10'	(1) 2x4x16'	(1) 1x4x12' (Hem.)
(12) 1x6x10'	(2) 2x4x14'	(2) 1x6x8'	(1) 1x12x10'	(2) 2x4x12'	(1) 2x6x10' (Hem.)
	(2) 2x4x12'	(1) 1x8x14'	(2) 1x8x10'	(1) 1x8x10'	(1) 2x6x10' (Hem.)
				(1) 1x4x10'	
				(4) 1x4x14'	(1) 1x12x10' (Pine)
				(1) 1x4x10'	
				(1) 1x8x10' (Rip to 1x7)	
				(1) 1x10x10' (Rip to 1x5)	

Pressure treated Three 1x6x10

Ramp Decking & stringers

Hardware and Millwork

16D Nails 5lbs of 3" common framing nails
 6d Nails 15lbs of 2 1/2" Galvanized siding trim nails
 Screws 5lbs of 1 5/8" Galvanized Deck Screws

Corrugated Metal Roof

Five @ 85"
 Five @ 42"
 16 ln ft. of ridge cap
 250 Roofing Screws

If using Asphalt Roofing

Enough Sheathing for 160 sq feet Five Sheets of 5/8" CDX Plywood or Eleven 1x12x14 Boards any species
 160 Sq Ft of Roofing Shingles (6 bundles)



Hardware Package

Contact us today to purchase a Hardware Package to match this set of plans.

Suggested Tools	
Skill Saw or Hand saw	Pencil
Saw-z-all or chain saw	Speed Square
Hammer	Four-foot level
Nail puller (cats paw or crow bar)	Cordless Drill
25' tape measure	1/4" drive bit for drill
Chalk line	#2 Phillips
Extension Cord	#3 Square Drive
Tin Snips	Razor Knife
Staple gun	Chisel



6x12 Woodbin Material List

Use this list as a shopping list.
 Rough sawn Lumber

Floor (Hemlock)	Walls (Hemlock)	Roof (Hemlock)	Siding (Pine)	Trim (Pine)	Extra
(2) 4x6x12'	(1) 4x4x12'	(7) 2x6x10'	(8) 1x12x12'	(1) 2x8x10'	(4) 1x4x8' (Hem.)
(9) 2x6x8'	(3) 4x4x14'	(5) 1x4x10'	(1) 1x12x12'	(2) 2x8x12'	(1) 1x4x12' (Hem.)
(2) 2x6x12'	(2) 4x4x12'	(3) 1x4x8'	(11) 1x12x10'	(1) 2x4x14'	(1) 2x6x10' (Hem.)
(13) 1x6x12'	(4) 2x4x14'	(2) 1x6x8'	(1) 1x12x10'	(2) 2x4x12'	(1) 1x12x10' (Pine)
	(3) 2x4x12'	(1) 1x8x14'	(2) 1x8x10'	(1) 1x8x10'	
				(1) 1x4x10'	
				(4) 1x4x14'	
				(1) 1x4x10'	
				(1) 1x8x10' (Rip to 1x7)	
				(1) 1x10x10' (Rip to 1x5)	

Pressure treated Three 1x6x10

Ramp Decking & stringers

Hardware and Millwork

- 16D Nails 6lbs of 3" common framing nails
- 8d Nails 6lbs of 2 1/2" Galvanized siding trim nails
- Corrugated Metal Roof
- Ten @ 42" : Rip last sheets on both ends
- 16 ln ft. of ridge cap
- 150 Roofing Screws

If using Asphalt Roofing

- Enough Sheathing for 160 sq feet Five Sheets of 5/8" CDX Plywood or Eleven 1x12x14 Boards any species
- 160 Sq Ft of Roofing Shingles (6 bundles)



Hardware Package

**Contact us today to purchase a
 Hardware Package to match
 this set of plans.**

Suggested Tools	
Skill Saw or Hand saw	Pencil
Saw-z-all or chain saw	Speed Square
Hammer	Four-foot level
Nail puller (cats paw or crow bar)	Cordless Drill
25' tape measure	1/4" drive bit for drill
Chalk line	#2 Phillips
Extension Cord	#3 Square Drive
Tin Snips	Razor Knife
Staple gun	Chisel



Jamaica Cottage Shop, Inc.
 Post Office Box 106 Jamaica, Vermont 05343
 Voice 802 297 3760 Fax 802 297 2825
plans@JamaicaCottageShop.com

6x16 Woodbin Material List

Please contact us with any mistakes or discrepancies in these plans. We strive to provide our clients with a quality product and encourage feedback.

Use this list as a shopping list.
 Rough sawn Lumber

Floor (Hemlock)	Walls (Hemlock)	Roof (Hemlock)	Siding (Pine)	Trim (Pine)	Extra
(2) 6x6x16'	(1) 4x6x16'	(8) 2x6x10'	(9) 1x12x12'	(1) 2x8x16'	(4) 1x4x8' (Hem.)
(2) 2x6x16'	(3) 4x4x16'	(7) 1x4x10'	(1) 1x12x14'	(2) 2x8x12'	(1) 1x4x12' (Hem.)
(7) 2x6x12'	(2) 4x4x12'	(4) 1x4x8'	(9) 1x12x10'	(1) 2x4x16'	(1) 2x6x16' (Hem.)
(12) 1x6x16'	(2) 2x4x16'	(2) 1x6x8'	(1) 1x12x16'	(2) 2x4x12'	(1) 2x6x16' (Hem.)
	(2) 2x4x12'	(1) 1x8x16'	(2) 1x8x10'	(1) 1x8x16'	(1) 1x12x16' (Pine)
				(1) 1x4x16'	
				(4) 1x4x14'	
				(1) 1x4x10'	
				(1) 1x8x14' (Rip to 1x7)	
				(1) 1x10x16' (Rip to 1x5)	

Pressure treated Three 1x6x10 Ramp Decking & stringers

Hardware and Millwork

- 16D Nails 5lbs of 3" common framing nails
- 6d Nails 15lbs of 2 1/2" Galvanized siding trim nails
- Screws 5lbs of 1 5/8" Galvanized Deck Screws
- Corrugated Metal Roof
- Five @ 86"
- Five @ 42"
- 16 ln ft. of ridge cap
- 300 Roofing Screws

If using Asphalt Roofing

- Enough Sheathing for 160 sq feet Five Sheets of 5/8" CDX Plywood or Eleven 1x12x14 Boards any species
- 160 Sq Ft of Roofing Shingles (6 bundles)



Hardware Package

Contact us today to purchase a Hardware Package to match this set of plans.

Suggested Tools	
Skill Saw or Hand saw	Pencil
Saw-z-all or chain saw	Speed Square
Hammer	Four-foot level
Nail puller (cats paw or crow bar)	Cordless Drill
25' tape measure	1/4" drive bit for drill
Chalk line	#2 Phillips
Extension Cord	#3 Square Drive
Tin Snips	Razor Knife
Staple gun	Chisel



8x8 Woodbin Material List

Floor

HEMLOCK

- (2) 4x6x8' Skids
- (9) 2x6x8' Floor Joists, Rim Joists
- (16) 1x6x8' Floor Boards

Framing

HEMLOCK

- (2) 4x4x10' Braces
- (8) 4x4x8' Posts, Beams
- (2) 2x4x14' Nailers
- (2) 2x4x10' Nailers
- (2) 1x4x10' Temp Bracing
- (2) 1x4x8' Temp Bracing

Roof

HEMLOCK

- (5) 2x6x12' Rafters
- (1) 1x8x8' Ledger Board
- (1) 1x6x10' Collar Ties
- (8) 1x4x8' Strapping

Siding

PINE

- (4) 1x12x12' Siding
- (10) 1x12x10' Siding
- (11) 1x12x8' Siding
- (1) 1x10x6' Siding
- (2) 1x8x8' Siding

Trim

PINE

- (3) 2x8x10' Fascia
- (1) 2x8x8' Fascia
- (3) 2x4x10' Shadow
- (1) 2x4x8' Shadow
- (2) 1x10x10' Door Casing (Rip to 5")
- (1) 1x8x10' Fascia
- (1) 1x8x8' Kick Plate (Rip to 7")
- (1) 1x4x12' Door Trim
- (2) 1x4x10' Door Trim, Shadow
- (8) 1x4x8' Corner Trim

Extra Lumber

PINE

- (1) 2x6x10' Extra Lumber
- (2) 1x12x10' Extra Lumber

Hardware

- (5lbs) 16D Framing Nails
- (2lbs) 16D HDG Nails
- (5lbs) 8D Nails
- (250) 1-1/2" Roofing Screws
- (1) 1/4" Hex Bit

Corrugated Metal Roofing

- (3) Pieces at 97"
- (3) Pieces at 42"
- (1) Ridge Cap at 110"



8x10 Woodbin - Shopping List

Floor Frame

Hemlock
2- 4x6x10' Skids
4- 2x6x10' Rim Joists
9- 2x6x8' Joists

Hemlock Flooring

16-1x6x10' Flooring

Posts & Beams

Hemlock
Angle Braces
4- 4x4x12'
1- 4x4x10'
8- 4x4x8'

Wall Framing

Hemlock
4- 2x4x12'

Siding

4 - 1x8x8' Pine Boards
12 - 1x12x8' Pine Boards
6 - 1x12x10' Pine Boards
1 - 1x12x12' Pine Boards

Doors

Pine Rough
9- 1x12x12' Pine

Ramp decking

Treated Lumber
4- 5/4x6x10'
2- 2x6x10' Stringers

Roof

Hemlock Rafters
10- 2x6x8'

Ridgepole

Hemlock
1- 1x8x10'

Collar Ties

Hemlock
3- 1x6x8'

Roof Strapping

Pine or Hemlock
8- 1x4x12'

Metal Roof

5 @ 97"
5 @ 42"
11 ½ Lineal Ft. of ridge cap
225 Green Wood Grip Screws

Windows, Trim

All Trim Pine
Windows Trim, Shadow, Corner, Door

1- 1x4x12'
12- 1x4x8'
3- 2x4x8'
1- 2x4x12'
3- 1x5x6'

Fascia

1- 1x8x12' (rear)
3- 2x8x8' (gable)
1-2x8x12'

Hardware

4-8" black T hinges
40-2" black hinge screws
1-Black turn latch
1-foot bolt #151-027
1-Chain bolt #150-771
1-#1 square drive bit
1-#2 square drive bit
8 lbs 16d nails for framing
8 lbs 6d galvanized nails
2 lbs 16d galvanized nails
2-6" window hooks
4-eyehooks
20-3/4" pan head screws for 4-
Black 3" window hinges
4 lb of 1 5/8" zinc drywall
screws for doors and window
stops

Suggested Tools:

Hammer
Pencil
Tape measure
Razor Knife
Chalk Line
Speed Square
Extension Cord
Circular Saw
4 foot level
Cordless drill
Philips bit
¼" drive for roofing screws
Tin Snips
Chisel

*Contact us today to
purchase a Hardware
Package to match this
set of plans.*

Please contact us with any
mistakes or discrepancies in
these plans. We strive to
provide our clients with a
quality product and
encourage feedback.



Jamaica Cottage Shop, Inc.
Post Office Box 106 Jamaica, Vermont 05343
Voice 802 297 3760 Fax 802 297 2825
plans@JamaicaCottageShop.com

8x12 Woodbin - Shopping List

Floor Frame

Hemlock
2- 4x6x12' Skids
4- 2x6x12' Rim Joists
7- 2x6x8' Joists

Hemlock Flooring

16-1x6x12' Flooring

Posts & Beams

Hemlock
Angle Braces
4- 4x4x12'
1- 4x4x10'
8- 4x4x8'

Wall Framing

Hemlock
3- 2x4x12'
1- 2x4x14'

Siding

4 - 1x8x8' Pine Boards
14 - 1x12x8' Pine Boards
6 - 1x12x10' Pine Boards
1 - 1x12x12' Pine Boards

Doors

Pine Rough
9- 1x12x12' Pine

Ramp decking

Treated Lumber
4- 5/4x6x10'
2- 2x6x10' Stringers

Roof

Hemlock Rafters
11- 2x6x8'

Ridgepole

Hemlock
1- 1x8x12'

Collar Ties

Hemlock
3- 1x6x8'

Roof Strapping

Pine or Hemlock
8- 1x4x12'

Metal Roof

5 @ 97"
5 @ 42"
13 ½ Lineal Ft. of ridge cap
275 Green Wood Grip Screws

Windows, Trim

All Trim Pine
Windows Trim, Shadow, Corner, Door

1- 1x4x14'
12- 1x4x8'
3- 2x4x8'
1- 2x4x14'
3- 1x5x6'

Fascia

1- 1x8x14' (rear)
3- 2x8x8' (gable)
1-2x8x14'

Top doorstep

1- 1x2x12'
1-1x2x8'

Window stops

2-1x3x8'

Hardware

4-8" black T hinges
40-2" black hinge screws
1-Black turn latch
1-foot bolt #151-027
1-Chain bolt #150-771
1-#1 square drive bit
1-#2 square drive bit
8 lbs 16d nails for framing
8 lbs 6d galvanized nails
2 lbs 16d galvanized nails
2-6" window hooks
4-eyehooks
20-3/4" pan head screws for 4-
Black 3" window hinges
4 lb of 1 5/8" zinc drywall
screws for doors and window
stops

Millwork:

12x12 Wood louvered vent
2-2x2 6 light barn sash
windows

Suggested Tools:

Hammer
Pencil
Tape measure
Razor Knife
Chalk Line
Speed Square
Extension Cord
Circular Saw
4 foot level
Cordless drill
Philips bit
¼" drive for roofing screws
Tin Snips
Chisel

*Contact us today to
purchase a Hardware
Package to match this
set of plans.*

Please contact us with any mistakes or discrepancies in these plans. We strive to provide our clients with a quality product and encourage feedback.



Jamaica Cottage Shop, Inc.

170 Winhall Station Rd. South Londonderry, VT 05155

(802) 297 3760 plans@JamaicaCottageShop.com

8x16 Woodbin - Shopping List

Floor Frame

Hemlock
2- 4x6x16' Skids
2- 2x6x16' Rim Joists
13- 2x6x8' Joists

Flooring

16-1x6x16' Hemlock Boards

Posts & Beams

Hemlock
2- 4x4x16'
2- 4x4x10'
9- 4x4x8'

Wall Framing

Hemlock
8- 2x4x8'

Siding

4 - 1x6x8' Pine Boards
4 - 1x8x8' Pine Boards
22 - 1x12x8' Pine Boards
12 - 1x12x10' Pine Boards
3 - 2x8x8' Pine (battens)
1 - 2x8x10' Pine (battens)

Doors

Pine Rough
9- 1x12x12' Pine

Ramp decking

Treated Lumber
4- 5/4x6x10'
2- 2x6x10' Stringers

Bird Blocking

1- 1x12"x14' Pine

Roof

Hemlock Rafters
14- 2x6x8'

Ridgepole

Hemlock
1- 1x8x16'

Collar Ties

Hemlock
2- 1x6x10'

Roof Strapping

Pine or Hemlock
16- 1x4x8'

Metal Roof

6 @ 97"
6 @ 42"
18 Lineal Ft. of ridge cap
300 Green Wood Grip Screws

Trim

All Trim Pine
Shadow, Corner, Door

16- 1x4x8'
5- 2x4x8'

Fascia

2- 1x8x10' (rear)
5- 2x8x10' (gable/front)

Door Casing

2 - 1x5x12'

Hardware

4-8" black T hinges
40-2" black hinge screws
1-Black turn latch
1-foot bolt #151-027
1-Chain bolt #150-771
1-#1 square drive bit
1-#2 square drive bit
8 lbs 16d nails for framing
8 lbs 6d galvanized nails
2 lbs 16d galvanized nails
2-6" window hooks
4-eyehooks
16-3/4" pan head screws for
4 lb of 1 5/8" zinc drywall
screws for doors

Suggested Tools:

Hammer
Pencil
Tape measure
Razor Knife
Chalk Line
Speed Square
Extension Cord
Circular Saw
4 foot level
Cordless drill
Philips bit
1/4" drive for roofing screws
Tin Snips
Chisel

*Contact us today to
purchase a Hardware
Package to match this
set of plans.*

Please contact us with any mistakes or discrepancies in these plans. We strive to provide our clients with a quality product and encourage feedback.



Floor- Hemlock

2-6x6x20' Skids
2-2x6x12'
17-2x6x8'
16-1x6x16'
8-1x6x8'

Walls-Hemlock

5-4x4x14'
4-4x4x12'
2-4x4x12' Angle Braces
1-4x4x10' Angle Braces
2-4x4x8'
2-2x4x14'
1-2x4x12'
2-2x4x8'

Roof-Hemlock

11-2x6x12' Rafters
16-1x4x10' Strapping
4-1x6x8'
2-1x8x10' Pine

Temp Bracing/ Extra Lumber

1-2x4x10'
4-1x4x10'
1-2x6x10'
1-1x12x10'

Siding-Pine

3-1x12x16'
10-1x12x14'
13-1x12x10'
4-1x8x12'

Trim-Pine

3-2x8x12'
2-2x8x10'
3-2x4x12'
2-2x4x10'
1-1x8x12'
2-1x8x10' Rip to 7"
2-1x10x10'-Rip to 5"
2-1x4x16'
2-1x4x14'
2-1x4x12'
4-1x4x10'

Hardware and Millwork

7 - Metal Roof @92" Long
7-Metal Roof @ 42" Long
2-Pieces Ridge Cap @123"
1-Piece Ridge Cap@ 36"

10lbs- 16d Framing Nails
10lbs-6d HDG Nails
2lbs-16D Galv Nails
325- Roofing screws

1-#2 Sq drive bit
1-1/4" Hex bit

Suggested Tools:

Circular Saw or Hand saw
Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar) Pencil
25' Tape measure
Razor Knife
Chalk Line
Speed Square
Extension Cord
4 foot level
Cordless drill Philips bit
1/4" drive for roofing screws
Tin Snips
Chisel



10x20 Woodbin Material List

Floor- Hemlock

5-2x6x16' Skids& Rim Joists
10-2x6x12' Skids & Rim Joists
16-2x6x10' Joists
20-1x6x12' Decking
20-1x6x8' Decking

Walls-Hemlock

3-4x4x14' Posts & Angle Braces
5-4x4x12' Posts & Beams
3-4x4x10' Beams
2-2x4x14' Door Posts
8-2x4x10' Nailers & locking

Roof-Hemlock

4-2x6x12' Rafters
11-2x6x10' Rafters
2-1x12x10' Bird Blocking
1-1x8x12' Ridge
1-1x8x8' Ridge
5-1x6x8' Collar Ties
9-1x4x12' Strapping
9-1x4x8' Strapping

Temp Bracing/ Extra Lumber

4-1x4x12' Hemlock
1-1x4x10' Hemlock
1-1x4x6' Hemlock
1-1x12x12' - Pine
1-2x4x12' Hemlock

Siding-Pine

10-1x12x12'
15-1x12x10'
6-1x12x8'
1-1x8x10'
2-1x8x8'
1-1x6x10'
2-1x6x8'

Trim-Pine

2-2x8x12' Fascia
3-2x8x10' Fascia
2-1x8x12' Fascia
1-2x4x12' Shadow
4-2x4x10' Shadow
5-1x4x12' Shadow& Door Trim
2-1x4x10' Shadow Trim
6-1x4x8' Corner Trim
2-1x10x10' Rip to 5" For Casing
2-1x8x10' Rip to 7" For Kick Plates

Corrugated Roofing

7 Pieces of roofing @116"
7 Pieces of roofing @47"
2-Pieces Ridge Cap @126"
1-Pieces Ridge Cap @36"

Hardware

10bs-16D Framing Nails
5lbs-16D HDG Hand Nails-Galv
10lbs-8D HDG Hand Nails-Galv
400 -Roofing Screws
1-1/4" Hex Bit

Suggested Tools

Skill Saw or Hand saw Saw-z-all or chain saw
Hammer
Nail puller (cats paw or crow bar)
25' tape measure Chalk line Extension Cord
Tin Snips
Staple gun
Pencil
Speed Square Four-foot level Cordless Drill
1/4" drive bit for drill
#2 Phillips
#3 Square Drive Razor Knife Chisel



12x24 Woodbin Material List

Floor

HEMLOCK

- (15) 2x6x16' Skids / Rim Joists
- (19) 2x6x12' Floor Joists
- (18) 1x6x16' Floor Boards
- (24) 1x6x12' Floor Boards

Framing

HEMLOCK

- (1) 4x4x16' Beams
- (1) 4x4x14' Beam
- (13) 4x4x12' Posts / Beams / Braces
- (1) 4x4x10' Beam
- (2) 2x4x16' Nailers
- (1) 2x4x14' Nailers
- (2) 2x4x12' Nailers
- (6) 1x4x12' Temp Bracing
- (2) 1x4x10' Temp Bracing

Roof

HEMLOCK

- (13) 2x6x16' Rafters
- (3) 1x8x14' Collar ties
- (2) 1x8x12' Ridgepole
- (1) 1x8x10' Collar ties
- (10) 1x4x14' Strapping
- (10) 1x4x10' Strapping

Extra Lumber

HEMLOCK

- (1) 2x4x12' Extra Lumber
- (1) 2x6x12' Extra Lumber

PINE

- (1) 1x12x16' Extra Lumber

Siding

PINE

- (3) 1x12x16' Siding
- (14) 1x12x14' Siding
- (2) 1x12x12' Siding
- (14) 1x12x10' Siding
- (1) 1x12x8' Siding
- (2) 1x10x16' Siding
- (2) 1x10x10' Siding
- (1) 1x8x16' Siding

Trim

PINE

- (3) 2x8x16' Fascia
- (4) 2x8x10' Fascia
- (2) 2x4x16' Shadow
- (4) 2x4x14' Shadow
- (2) 1x10x10' Kickplate (Rip to 7")
- (3) 1x10x8' Door Casing (Rip to 5")
- (2) 1x4x16' Corner Trim
- (1) 1x4x14' Corner Trim
- (1) 1x4x12' Corner Trim
- (2) 1x4x16' Door Trim
- (1) 1x4x14' Door Trim

Hardware

- (10lbs) 16D Framing Nails
- (5lbs) 16D HDG Nails
- (10lbs) 8D Nails
- (700) 1-1/2" Roofing Screws
- (1) 1/4" Hex Bit

Corrugated Metal Roofing

- (9) Pieces at 139"
- (9) Pieces at 42"
- (2) Ridge Cap at 126"
- (1) Ridge Cap at 96"